


Note:

1. Approximately 1,700 s.f. of proposed 5'x5" PCC walk shall be constructed on a compacted 2" stone base.
2. A portion of existing walk shall be removed to adjust alignment.
3. Excavation to include area adjacent to proposed walk as required to provide smooth transition.
4. Existing asphalt path shall be patched (Item 18. Class D Patching- Various Types) between 7 and 14 days after sidewalk construction.
5. All disturbed landscape areas to be restored with seed and erosion control blanket within 7 days of asphalt path completion.



Quantities	
01. Portland Cement Contrete Sidewalk 5 Inch	1,700 s.f.
02. Detectable Warnings	24 s.f.
03. Sidewalk Removal	450 s.f.
08. Shotcrete Curb & Gutter Repair	14 l.f.
14. Washout Basin	1 ea.
15. Earth Excavation	50 c.y.
18. Class D Patches- Various Types	2 ton
20. Aggregate Base Course, Type B	22 ton
28. Seeding, Class 1A (& Topsoil)	340 s.y.
29. Erosion Control Blanket	340 s.y.

Source: Esri, DigitalGlobe, GeoEye, i-cubed, USDA, USGS, AEX, Getmapping, Aerogrid, IGN, IGP, swisstopo, and the GIS User Community

PUBLIC WORKS DEPARTMENT
 Village of Orland Park
 15655 Ravinia Avenue
 Orland Park, IL 60462
 (708) 403-6350
 publicworks@orland-park.il.us

183rd Street Sidewalk Construction

This map is for reference only. The Village makes no representations as to the accuracy of the depicted utility locations or sizes. The data is subject to change without notice. The Village of Orland Park assumes no liability in the use or application of the data. Reproduction or redistribution is forbidden without the expressed written consent from the Village of Orland Park.

